



---

## 1. Basic System Configuration

ITEM	SPECIFICATION
System Type	PLASMA CLEANER / PSK Supra 3

ITEM	SPECIFICATION
Equipment Model	SUPRA III
Manufacturer	PSK Inc.
Wafer Size	300mm (12 inch)
Applied Tech Node	70nm ~ 10nm Process Technology
Plasma Type	Remote Plasma

## 2. System Configuration

Substrate Type	Silicon Wafer
System Control	COMPUTER CONTROL / PLC & PC Based Control
Operating System	Windows 10 Operating System
Control Sub-Module	ELECTRIC RACK
Signal Lamp	SIGNAL LAMP
Buzzer	Alarm System Installed
Main Frame	STEEL FRAME, ALL SIDE COVER EASY TO INSTALL AND REMOVE
System Cover	Minimize Main System Footprint
Overall Requirement	REQUIREMENT OVERALL PREP FOR SYSTEM

## 3. Chamber Specifications

<b>Process Chamber</b>	PROCESS CHAMBER - 2 Chambers Configuration
<b>Chamber Material</b>	ONE PIECE ALUMINUM BODY HARD ANODIZED THICKNESS $\geq 40\mu\text{m}$
<b>Surface Finish</b>	SURFACE FINISHED
<b>View Port</b>	TWO PORT FOR EACH PROCESS CHAMBER
<b>Transfer Module</b>	TRANSFER MODULE
<b>Wafer Handling</b>	WAFER HANDLING / CLEANING MODULE
<b>Align Module</b>	ALIGN MODULE / COOLING MODULE
<b>Cooling Module</b>	COOLING MODULE
<b>Load Port</b>	LOAD PORT - Wafer Loading Interface
<b>EFEM Robot</b>	EFEM ROBOT - Auto Wafer Transfer
<b>Handle &amp; Vacuum Chucking</b>	GAS FOR HANDLE, VACUUM CHUCKING TWO FORKS, VACUUM CHUCKING
<b>Throughput</b>	100 WPH (Wafers Per Hour)

## 4. Pressure Control System

<b>Process Chamber Pressure</b>	PROCESS CHAMBER
<b>Base Pressure</b>	PROCESS CHAMBER BASE PRESSURE - High Vacuum Achievement
<b>Process Control Gauge</b>	PROCESS CONTROL GAUGE
<b>Chamber Vacuum Status</b>	CHAMBER VACUUM STATUS - Real-time Monitoring
<b>Chamber Pressure</b>	CHAMBER PRESSURE
<b>Pressure Gauge</b>	CPD mTorr (Capacitance Manometer & Isolation Valve) CAPACITANCE MANOMETER & ISOLATION

	VALVE VACUUM GAUGE & ISOLATION VALVE VACUUM SWITCH
Gate Valve	GATE VALVE - Chamber Isolation Valve
Pressure Control	PRESSURE CONTROL - Precision Adjustment
Control Method	AUTO/MANUAL CONTROL BY SOFTWARE
Pressure Control Valve	PRESSURE CONTROL VALVE
Vacuum Pump Config	VACUUM PUMP CONFIGURATION
Process Chamber Vacuum	PROCESS CHAMBER - Independent Vacuum System
Vacuum Pump	VACUUM PUMP - DRY PUMP
Pressure Range	1 ~ 2,000 mTorr

## 5. Gas Supply System

Gas Lines	6 Gas Lines
Process Chamber Gas	Dedicated Gas Supply for PROCESS CHAMBER
Gas Types	GAS 1: O <sub>2</sub> (Oxygen) GAS 2: N <sub>2</sub> (Nitrogen) GAS 3: AR (Argon) GAS 4: CF <sub>4</sub> GAS 5: H <sub>2</sub> GAS 6: Selectable Gas (Other Process Gas)  * Gas specifications may vary depending on the equipment.
Methodology	Settings per Chamber (Independent Control)
Gas Panel	21PS-HER-LIS-Chamber Type (Dedicated Gas Panel)

## 6. RF System

<b>RF Power</b>	REMOTE RF PLASMA
<b>RF Frequency</b>	13.56 MHz (Standard RF Frequency)
<b>RF Output</b>	Max 5,000 Watts (5 kW)
<b>Control Method</b>	Software-based Auto/Manual Control

## 7. Control System & Interface

<b>Control System</b>	PLC & PC Based Integrated Control
<b>User Interface</b>	21-inch Touch Panel TFT
<b>Operating System</b>	Windows 10 Operating System
<b>Process Control</b>	Recipe-based Auto Process Control
<b>Data Logging</b>	Real-time Process Data Recording & Monitoring

## 8. Equipment Layout & Installation Dimensions

<b>Component</b>	<b>Dimensions (Unit: mm)</b>
<b>Main Body</b>	W2150 x L3500 x H2150 (Width 2,150mm x Length 3,500mm x Height 2,150mm)
<b>E-Rack 1 (Electric Rack 1)</b>	W600 x L900 x H1900 (Width 600mm x Length 900mm x Height 1,900mm)
<b>E-Rack 2 (Electric Rack 2)</b>	W600 x L900 x H1900 (Width 600mm x Length 900mm x Height 1,900mm)
<b>Total Layout (Incl. Maintenance)</b>	<b>W5150 x L6700 x H2150</b> (Width 5,150mm x Length 6,700mm x Height 2,150mm)

## 9. Utility Requirements

Utility Item	Specifications
<b>Electric</b>	3Ø 208V, 250A 3-Phase 208 Volts, 250 Amperes
<b>CDA</b> <b>(Clean Dry Air)</b>	7 kgf/cm <sup>2</sup> Clean Dry Air - 7 kgf/cm <sup>2</sup>
<b>PCW</b> <b>(Process Cooling Water)</b>	4 kgf/cm <sup>2</sup> , 20 LPM Process Cooling Water - 4 kgf/cm <sup>2</sup> , 20 LPM
<b>Gas</b>	Chamber Gas Line Check Chamber Gas Line Check (O <sub>2</sub> , N <sub>2</sub> , AR, CF <sub>4</sub> , H <sub>2</sub> , etc.)
<b>Vacuum</b>	Robots Wafer Chucking Vacuum System for Robot Wafer Chucking